







NAROČNIK: Občina Šentjur	SESTAVIL: A. Matič	LIST ŠT: 1 od 1
IZVAJALEC: 	ŠT. PROJEKTA: 863/18	
	DATUM: januar 2019	
OBJEKT: STANOVANJSKI OBJEKT - HIŠA OBREŠNIK	ŠT. RISBE: P.4	
ELEMENT: AB VENEC	ŠIFRA:	

POZ	ŠT.KOM	φ	TIP	L (m)	OBLIKA PALICE	SUMA L (m)	SUMA KG
1	245	12	3	3.44		842.50	767.79
2	42	14	3	12.00		504.00	625.97
3	14	14	3	2.60		36.40	45.21
4	28	14	3	7.30		204.40	253.86
5	20	14	3	2.30		46.00	57.13
6	12	14	3	2.50		30.00	37.26

REKAPITULACIJA:

TIP 3 = RA 400/500-2

m                      kg

φ12      842.50      767.79

φ14      820.80      1019.43

---

Suma za TIP 3:      1663.30      1787.22

	kg
<= φ12:	767.79
>= φ14:	1019.43
Skupna suma:	1787.22